

John Street Activity 2019

Listed below are the activities we anticipate conducting in the John Street area during the remaining months of 2019. The dates are best estimates and are dependent on weather, lab availability, and other factors.

- John Street Interim Remedial Measure (IRM):
 - Starting the first full week in November, we will receive delivery of materials (carbon) for the IRM at the John Street property. The following week, contractors will begin work to inject the carbon mixture into new temporary injection wells on the property. The carbon will limit Volatile Organic Compounds (VOCs) movement from the site. We anticipate being done with the work by Thanksgiving.
 - Approximately one month later in mid-December, groundwater samples will be collected from wells on and near the John Street property and analyzed for VOCs to monitor the effectiveness of the IRM.
- Additional sub slab depressurization systems will be installed later this year in several residences along Lyman Street.
- Construction-type activity will occur at 80 First Street as Oak-Mitsui will be draining water from the holes on site and later using heavy equipment to fill in the holes. Clean soil also will be brought to the site in dump trucks as needed.
- Environmental crews will identify potential John Street drip line soil sampling locations within about 1,000 feet of John Street.
- Our consultant will be flying a drone near the Hoosick River to take high-resolution photographs and thermal images to identify potential groundwater discharges along the river's edge.
 - Tentatively scheduled for later this year.

PLEASE NOTE: All of this work will be done under the supervision of the NYSDEC and the New York State Department of Health. There also is ongoing work in the area associated with the Village's sewer project.

Contact: Victoria Streitfeld for Honeywell Community Relations at 609.218.9460.